

Capsule Summary

Inventory No. F-6-98

San Marino

15828 Motter Station Road

Frederick County, MD

Ca. 1812 and c.1850 (house); 1946 (dairy barn)

Access: Private

Addendum to Description (1991)

Eight buildings continue to be contributing buildings to this site: Main House, Gothic Revival Privy, Smokehouse, Concrete Block Barn and Dairy Shed, Wood Shed/Blacksmith Shop, and Two Agricultural Sheds. The Stone Outbuilding and Frame Barn were torn down and replaced.

Buildings not included in the 1991 description that contribute to the site are: Wagon shed/Corncrib, Stone and Frame Storage, Hog Pen, Wire Corn Crib and Metal Granary. San Marino is significant under Criterion C as an example of the use of distinct Gothic Revival stylistic elements from the mid-19th century to update the elegant Georgian form of a late 18th century dwelling. The San Marino farmstead is significant under Criterion A for its eclectic collection of agricultural and domestic buildings from several different periods of ownership and farm production. The significance of San Marino as a remarkable example of the melding of Georgian and Gothic Revival architectural elements is embedded in the history of the northern Frederick County rural neighborhood around Mt. Saint Mary's College. One of several relatively high-styled houses in the area, each appears to have been operated as "gentlemen's farm" by one of several wealthy families associated with Mt. St. Mary's College. All of the farms find their roots

F-6-98

in the land of 18th century settler, William Elder, known as *Pleasant Level*, the mid-19th century ownership of Dr. James A. Shorb, and its subdivision under Joshua Shorb.

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No. F-6-98

1. Name of Property

(indicate preferred name)

historic

San Marino

(MIHP update)

other

2. Location

street and number 15828 Motter Station Road

not for publication

city, town Emmitsburg

☒ vicinity

county Frederick

3. Owner of Property

(gives names and mailing addresses of all owners)

name Dorothy E. Little et al (Donald Moser)

street and number 15828 Motter Station Road

telephone

city, town Emmitsburg

state MD

zip code 21727

4. Location of Legal Description

courthouse, registry of deeds, etc. Frederick Co. Courthouse

liber 2282

folio 493

city, town Frederick

tax map 14

tax parcel 7

tax ID number N/A

5. Primary Location of Additional Data

- ☐ Contributing Resource in National Register District
- ☐ Contributing Resource in Local Historic District
- ☐ Determined Eligible for the National Register/Maryland Register
- ☐ Determined Ineligible for the National Register/Maryland Register
- ☐ Recorded by HABS/HAER
- ☐ Historic Structure Report or Research Report at MHT
- ☒ Other: Maryland Inventory of Historic Properties

6. Classification

Category		Ownership	Current Function		Resource Count	
<input type="checkbox"/> district		<input type="checkbox"/> public	<input checked="" type="checkbox"/> agriculture	<input type="checkbox"/> landscape	Contributing	Noncontributing
<input checked="" type="checkbox"/> building(s)		<input checked="" type="checkbox"/> private	<input type="checkbox"/> commerce/trade	<input type="checkbox"/> recreation/culture	11	5 buildings
<input type="checkbox"/> structure		<input type="checkbox"/> both	<input type="checkbox"/> defense	<input type="checkbox"/> religion	3	sites
<input type="checkbox"/> site			<input checked="" type="checkbox"/> domestic	<input type="checkbox"/> social	14	structures
<input type="checkbox"/> object			<input type="checkbox"/> education	<input type="checkbox"/> transportation	5	objects
			<input type="checkbox"/> funerary	<input type="checkbox"/> work in progress		Total
			<input type="checkbox"/> government	<input type="checkbox"/> unknown		
			<input type="checkbox"/> health care	<input type="checkbox"/> vacant/not in use		
			<input type="checkbox"/> industry	<input type="checkbox"/> other:		
					Number of Contributing Resources previously listed in the Inventory	
					10	

7. Description

Inventory No. F-6-98

Condition

<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated
<input type="checkbox"/> good	<input type="checkbox"/> ruins
<input checked="" type="checkbox"/> fair	<input type="checkbox"/> altered

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

Addendum to Description (1991)

Main House – The main house remains unchanged from its description in 1991. 1 contributing building. Immediately southwest of the house is a steel frame windmill structure, no long in operation. This is considered a contributing structure.

Gothic Revival Privy – The privy building was originally a two-room building, one room for the multiple-seat privy, the other served as a bathing room. The building stands on the high east bank of Beaver Branch, from which the bath water was supposedly drawn. The rooms were plastered over lath, divided by a partition wall. This wall was removed c.1947 by the Moser family and the building was used as a chicken brooder house. The building has suffered substantial deterioration since the 1990s. 1 contributing building.

Smokehouse – unchanged. 1 contributing building.

Stone Outbuilding – This building no longer stands. It has been replaced with a frame, shed roof wood shed with corrugated metal sheet siding. 1 non-contributing building.

Concrete Block Barn and Dairy Shed – These two buildings, a large Dairy Barn and small Milk House, are constructed of rusticated concrete block (not covered with formstone) with frame barrel roofs and flared eaves. The gable ends are sheathed with vertical board siding. A one-story, one-room, gable front addition, also rusticated concrete block, projects from the south elevation of the dairy barn. The barn and milk house are attached by a breeze-way. The milk house houses a large milk tank. The barn was reportedly built in 1946 and serviced a herd of up to 70 cows. 2 contributing buildings.

"Other outbuildings" (1991)

Wood shed/blacksmith shop – This was described in 1991 as "a new wood shed of board and batten siding with a gable roof of corrugated tin." The building is a timber frame construction with side gables and a central opening. Siding appears to be both plain vertical boards and board and batten. The building is said to have been moved to its current location prior to the Moser purchase in 1947. It was reportedly used as a blacksmith shop at one time. It now serves as a wood storage shed. 1 contributing building.

Frame Barn – Presumably this referred to the large one-story Utility Barn at the center of the agricultural complex. This building is constructed of military surplus steel drainage pipes welded together to form the barn frame and rafters. The barn's northwest corner incorporates the remaining stone bank foundation of an earlier bank barn at this location. The historic barn

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No. F-6-98

Name San Marino
Continuation Sheet

Number 7 Page 1

measured 100 feet by 50 feet; it was torn down by the present owner after it was damaged in a windstorm. Attached to the rear (north) elevation of the utility barn is a frame, shed roof Stall Barn. The building has a concrete foundation and vertical board siding. It is built along the west face of the access bank of the old bank barn and the remaining north section of the foundation wall (previously noted). This building contains the cattle stalls typically found in the lower level of a bank barn. Although contributing to the current operation of the farm, the relatively new construction makes this building non-contributing. 1 non-contributing building.

Two agricultural sheds – This probably refers to the Ensilage House and the Machine/Wood Shop, both located immediately south of the Utility Barn. The Ensilage House is a long, narrow, frame building on a raised concrete block foundation with poured concrete buttresses. Siding is horizontal weatherboard. The building was constructed to house silage, ground corn feed for livestock, more commonly kept in silos or in ensilage pits. It now serves as an equipment shed. The Machine/Wood Shop is a frame, gable front building on concrete block foundation, with board and batten siding. It is a large, one-room workshop. Attached to the north elevation of the Shop is a frame equipment shed, which also abuts the Utility Barn. 2 contributing buildings.

Buildings not included in the 1991 description

Wagon shed/Corncrib – Located at the southeast corner of the Utility Barn is a very long, frame wagon shed/corncrib combination building. Set on concrete block piers, the corncrib sides are covered with horizontal slats. The corrugated metal roof has four trap openings on each side; these are used to fill the cribs with corn. The building is still used for this purpose. 1 contributing building.

Stone and Frame Storage Building – Among a small complex of older buildings located north of the Utility Barn is this gable end building. The north and east walls are constructed of stone, while the south and west walls are frame. The west gable end is covered with board and batten siding. The building's original use is unknown, possibly hay or fruit storage. It is in very poor condition. 1 contributing building.

Hog Pen – The Hog Pen is a frame, gable end building with board and batten siding. 1 contributing building.

Wire Corn Crib and Metal Granary – Immediately west of the Hog Pen and Storage Building are the c.1930 corncrib and granary. Both have a conical metal sheathed roof. 2 contributing structures.

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No. F-6-98

Name San Marino
Continuation Sheet

Number 7 Page 2

Quonset Equipment Shed – This large, metal Quonset hut-style building is 100 feet by 50 feet. It is used for storage of equipment and hay or straw round bales. It has a large sliding door on a frame track. Although the building contributes to the current farming operation, its age requires that this be a non-contributing resource. 1 non-contributing building.

Trailer – Two decrepit mobile homes serve as goat houses on the farm. Both are considered non-contributing.

Open Stalls – The large pole shed stands to the northeast of the barn complex. Commonly called a “loafing shed” it provides shelter for livestock. Really just a series of poles supporting a roof, pole sheds are generally considered non-permanent, and though contributing to the operation of the farm, are not counted.

8. Significance

Inventory No. F-6-98

Period	Areas of Significance	Check and justify below			
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> health/medicine	<input type="checkbox"/> performing arts	
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> archeology	<input type="checkbox"/> education	<input type="checkbox"/> industry	<input type="checkbox"/> philosophy	
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> engineering	<input type="checkbox"/> invention	<input type="checkbox"/> politics/government	
<input checked="" type="checkbox"/> 1900-1999	<input type="checkbox"/> art	<input type="checkbox"/> entertainment/	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion	
<input type="checkbox"/> 2000-	<input type="checkbox"/> commerce	<input type="checkbox"/> recreation	<input type="checkbox"/> law	<input type="checkbox"/> science	
	<input type="checkbox"/> communications	<input type="checkbox"/> ethnic heritage	<input type="checkbox"/> literature	<input type="checkbox"/> social history	
	<input type="checkbox"/> community planning	<input type="checkbox"/> exploration/	<input type="checkbox"/> maritime history	<input type="checkbox"/> transportation	
	<input type="checkbox"/> conservation	<input type="checkbox"/> settlement	<input type="checkbox"/> military	<input type="checkbox"/> other: _____	
Specific dates	c.1812-1953	Architect/Builder	unknown		
Construction dates	c.1812 and c.1850 (house); 1946 (dairy barn)				
Evaluation for:					
<input type="checkbox"/> National Register	<input type="checkbox"/> Maryland Register	<input checked="" type="checkbox"/> X	not evaluated		

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance projects, complete evaluation on a DOE Form – see manual.)

Addendum to Significance (1991)

San Marino is significant under Criterion C as an example of the use of distinct Gothic Revival stylistic elements from the mid-19th century to update the elegant Georgian form of a late 18th century dwelling. The San Marino farmstead is significant under Criterion A for its eclectic collection of agricultural and domestic buildings from several different periods of ownership and farm production. The significance of San Marino as a remarkable example of the melding of Georgian and Gothic Revival architectural elements is embedded in the history of the northern Frederick County rural neighborhood around Mt. Saint Mary's College. One of several relatively high-styled houses in the area, each appears to have been operated as "gentlemen's farm" by one of several wealthy families associated with Mt. St. Mary's College. All of the farms find their roots in the land of 18th century settler, William Elder, known as *Pleasant Level*, the mid-19th century ownership of Dr. James A. Shorb, and its subdivision under Joshua Shorb.

The surprisingly flat terrain at the eastern base of Carrick's Knob, part of the Catoctin Mountain Range, provided a productive plantation for early settler to the area, William Elder. Elder emigrated from Maryland's Eastern Shore county, St. Mary's around the middle of the 18th century where he established his plantation known as *Pleasant Level*.¹ A devout Catholic, William Elder reportedly named the eastern face of Carrick's Knob, "St. Mary's Mount," where Mt. St. Mary's College would later be established in 1808. Other Catholic families followed the Elders from the Eastern Shore, and a number of students as well as professors settled in the area in the ensuing decades. These farms, with their elegant titles and stylish dwellings dotted the mid 19th century landscape of northern Frederick County:

Not forty rods from *Thornbrook*...is *San Marino* on its fair eminence; half a mile up the slope is Norman-like *Clairvaux*; in sight are *Hayland*, *Pleasant Level*, *Rosario*; beyond is *Inglewood*...; along the road are *Hillside*, *La Salette*, *Andorra*,

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No. F-6-98

Name San Marino
Continuation Sheet

Number 8 Page 1

Loretto, Mt. Carmel, San Jose, Santa Maria, Tanglewood. Almost every cottage eloquent of the taste and piety of the builders of the Mount...²

Among these various "cottage" farms, four were associated with William Elder's plantation, Clairvaux, Hayland, San Marino, and Thornbrook. Prominent Emmitsburg physician, Dr. James A. Shorb had been one of the original students at Mt. St. Mary's College. Staying in the area, he purchased at least part of the Elder plantation. Shorb reportedly replaced the old mansion house of William Elder with the Gothic Revival, Normanesque chateaux known as Clairvaux around 1850.³ At the same time, through the trusteeship of Joshua Shorb, Dr. James Shorb began subdividing the land among fellow Catholics, including Hayland, which became the home of William Miles, and later, Thornbrook, home of William's son, George Miles, former student and later instructor of English literature at the college.⁴

San Marino, probably constructed c.1780 as the home of one of Elder's sons, already had an elegant brick dwelling in place when James Shorb transferred the 200-acre farm to Joshua Shorb in 1853.⁵ Joshua Shorb, listed as Master Carpenter in the 1860 census, appears to have had the largest, and apparently one of the most successful carpentry businesses in the Emmitsburg District.⁶ Indeed, Joshua Shorb was listed among the leading builders of Emmitsburg in James A. Helman's 1906 *History of Emmitsburg, Md.*⁷ Although Joshua Shorb apparently lived in the town of Emmitsburg, it seems likely that he added the numerous Gothic Revival architectural elements to the brick house and probably constructed the Gothic chapel-like bathhouse/privy as well.

Joshua Shorb appears to have taken on several partners in the ownership of San Marino. Listed among the grantors in 1858, when the farm was again sold, were John M. Caffrey and Edward Tiers.⁸ Edward Tiers was a graduate of Mt. St. Mary's College and classmate of George Miles' (Thornbrook). Miles later married Adeline Tiers, Edward Tiers' daughter.⁹ A 1911 history of the region described Tiers as the owner of San Marino in the 1850s and it may be that Tiers, a New York City resident, purchased an interest in the farm in preparation for another daughter's marriage to Charles Manning. In 1858, Manning purchased San Marino for just over \$7,000.¹⁰

The Manning's owned and occupied San Marino for more than thirty years. The wide, flat fields of the 200-acre farm must have produced significant wheat crops; Manning's 100-foot long bank barn would have been one of the larger barns in the county. The farm passed to Manning's heirs in 1884, but was held up in Equity Court for unknown reasons. In 1895, probably following Manning's death, the farm was sold through the Frederick County Court of Equity.¹¹ Purchaser, Jonas Summers, only held San Marino for five years, selling it in 1900 to Daniel F. Roddy for \$8,000.¹²

Daniel Roddy was highlighted in Williams' *History of Frederick County* in 1910 as, "proprietor of Roddy's Limekilns, and owner of 'San Marino,' a beautiful farm near Emmitsburg, Md..."¹³ Located along the southern boundary of the farm, on what is now Old Kiln Road, the limestone quarry and kilns were operated by Roddy for several decades. In 1940,

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No. F-6-98

Name San Marino
Continuation Sheet

Number 8 Page 2

following Roddy's death, his widow sold the quarry to Clairvaux neighbor, Marie Gloninger Rail. The remaining 191 acres of San Marino were purchased by Ella K. Cramer.¹⁴

In 1941, Mrs. Cramer conveyed the San Marino farm to her children, James Cramer and a married daughter, Katherine C. Winebrener.¹⁵ The Winebrener's began the process of converting the farm to dairy production with the addition of the dairy barn and milk house adjoining the large bank barn already in place. In 1947, however, they too sold the farm; Donald and Emily Moser purchased the dairy farm with its elegant mansion house and continued dairy operations until 1997.¹⁶ Today the farm continues under cultivation but livestock consists of only a small number of beef cattle, horses, and goats.

Note: For Historical Context, please refer to *An Agricultural History of Mid-Maryland*, a Maryland Historical Trust grant funded context development project administered through The Catocin Center for Regional Studies, 2002-2003.

9. Major Bibliographical References

Inventory No. F-6-98

Frederick County Land Records, Frederick Co. Courthouse, Frederick, MD.
Helman, James A. *History of Emmitsburg, Maryland*. Frederick, MD: Citizen Press, 1906, reprinted 1975, Chronicle Press.
Meline, Mary M. and Edward F.X. McSweeney. *The Story of the Mountain*. Vol. II, Emmitsburg, MD: Weekly Chronicle, 1911.
Scharf, J. Thomas. *History of Western Maryland*. 1882, Bowie, MD: Heritage Books, Inc., 2002 CD-ROM.
Williams, T.J.C. *History of Frederick County, Maryland*. 1910; Baltimore, MD: Regional Publishing Co., 1979, reprint.

10. Geographical Data

Acreage of surveyed property Approx. 180 acres
Acreage of historical setting Approx. 5 acres
Quadrangle name Emmitsburg Quad Quadrangle scale 1:24,000

Verbal boundary description and justification

The boundary is defined by the boundaries shown on Frederick County Tax Map 14, Parcel 7.

11. Form Prepared by

name/title Paula S. Reed, PhD., Architectural Historian; Edie Wallace, Historian
organization Paula S. Reed & Associates, Inc. date 14 April 2003
street & number 105 N. Potomac Street telephone 301-739-2070
city or town Hagerstown state Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
DHCD/DHCP
100 Community Place
Crownsville, MD 21032-2023
410-514-7600

Maryland Historical Trust

Maryland Inventory of Historic Properties Form

Inventory No. F-6-98

Name San Marino
Continuation Sheet

Number 9 Page 1

¹ J. Thomas Scharf, *History of Western Maryland*, (1882, Bowie, MD: Heritage Books, Inc., 2002 CD-ROM), p. 581; *Clairvaux*, manuscript history, San Marino file, Frederick Co. Planning and Zoning preservation office.

² Mary M. Meline and Edward F.X. McSweeney, *The Story of the Mountain*, Vol. II, (Emmitsburg, MD: Weekly Chronicle, 1911), p. 101.

³ Clairveaux burned in 1970. Although Dr. J.A. Shorb lived at Clairveaux, he eventually moved to California where the town of San Marino was established. Clearly he felt a connection with the western Maryland farm and may have occupied the house while Clairveaux was under construction.

⁴ Ibid, pp. 104-105.

⁵ Frederick Co. Deed Book ES 4, page 31.

⁶ 1860 U.S. Population Census, Emmitsburg 5th District, Frederick Co., Maryland, microfilm collection, Frederick Co. Library, Frederick, MD. The census shows his personal property (exclusive of real estate) was valued at \$18,000, indicating he owned a substantial amount of equipment associated with his carpentry business.

⁷ James A. Helman, *History of Emmitsburg, Maryland*, (Frederick, MD: Citizen Press, 1906, reprinted 1975, Chronicle Press), p. 67.

⁸ Frederick Co. Deed Book BGF 2, page 514. This John M. Caffrey is probably Rev. John McCaffrey, president of Mt. St. Mary's College beginning in 1838 (Scharf, p. 591).

⁹ Meline and McSweeney, p. 105.

¹⁰ Frederick Co. Deed Book BGF 2, page 514; personal communication, Linda Franklin, *Thornbrook* owner and Miles descendant, May 2001.

¹¹ Frederick Co. Deed Books ECW 6, page 357 and JLJ 11, page 412.

¹² Frederick Co. Deed Book DHH 5, page 616.

¹³ T.J.C. Williams, *History of Frederick County, Maryland*, (1910; Baltimore, MD: Regional Publishing Co., 1979, reprint), Vol. II, p. 1013.

¹⁴ Frederick Co. Deed Book 428, page 29. This deed references the sale of the quarry to Marie Rail but does not provide a book and page reference.

¹⁵ Frederick Co. Deed Book 433, page 144.

¹⁶ Frederick Co. Deed Book 462, page 101. The most recent deed transfer (2282/493) was from Donald Moser to his children, although Mr. Moser continues to occupy the farm. This kind of transfer has become common among farming families in order to avoid crippling inheritance taxes.

QUONSET

F-6-98
SAN MARINO
FREDERICK CO., MD
SITE PLAN
(NOT TO SCALE)



OPEN (FREE)

STALLS

HOG
PEN

CORN
CRIB

GRAN-
ARY

STONE + FRAME
BUILDING

STALLS

SHED

OPEN

UTILITY BARN

OPEN

CORRAL

ENSILAGE SHED

SHED

WDRX
SHOP

CORN CRIBS

WAGON SHED

DAIRY
BARN

MILK
HOUSE

BLACKSMITH
SHOP?

SMOKEHOUSE



NEW
WOODSHED

BATH HOUSE/
PRIVY



MAIN
HOUSE

EQUIPMENT SHED

SABILLASVILLE


Scale 300 ft to an inch.

GRAHAM

Scale 800 ft to an inch.

LEWIS


Scale 800 ft to an inch.



EMMITTSBURG

DIST No. 3

Scale 1 1/2 inches to the mile




F-6-98, San Marino
Frederick Co., MD
1873 Atlas Map of Frederick Co.


MT. ST. MARY COLLEGE
1062/704
160.94 Ac.
P. 5

DON E. MOSER
462/101
187.14 A.
P. 7

F-6-98, San Marino
Frederick Co., MD
Tax Map 14, Parcel 7
Resource Boundary Map

17201/33
128.00A.
P.48







F-6-98

San Marino

Frederick Co., MD

E. Wallace

1/03

MDSHPO

Main house, S and E elevations, view NW

1/33



F-6-98

San Marino

Frederick Co., MD

E. Wallace

1/03

MDSHPO

Main house, E elevation, view W

2/33



F-6-98

San Marino

Frederick Co., MD

E. Wallace

1/03

MD SHPO

Main house, N and W elevations, view SE

3/33



F-6-98

San Marino

Frederick Co., MD

E. Wallace

1/03

MDSHPO

Main house, SE corner, porch detail

4/33



F-6-98

San Marino

Frederick Co., MD

E Wallace

1/03

MDSHPO

Main house, SE corner, detail

5/33



F-6-98

San Marino

Frederick Co., MD

E. Wallace

1-03

MDSHIPD

Smokehouse, W and S elevations, view NE

6/33



F-C-98

San Marino

Frederick Co, MD

E. Wallace

1-03

MD SHPO

Smokehouse, S and E elevations, view NW

7/33



F-6-98

San Marino

Fredrick C., MD

E. Wallace

1-03

MD5HPO

Smoke house, door hardware detail

8/33



F-6-98

San Marino

Frederick Co., MD

E Wallace

1/03

MDSHPO

Bathhouse/privy, S and E elevations, view NW

9/33



F-6-98

San Marino

Frederick Co., MD

E. Wallace

1-03

MDSHPD

Bathhouse/privy, interior, W wall

10/33



F-6-98

San Marino

Frederick Co., MD

E. Wallace

1/03

MDSHPO

new woodshed, view N.

11/33



F-6-98

San Marino

Frederick Co., MD

E. Wallace

1-03

MDSHPD

Old woodshed/blacksmith shop, S elevation, view N

12/33



F-6-98

San Marino

Frederick Co., MD

E. Wallace

1-63

MDSHPO

Dairy barn and milk house, W and Elevations,
view NE

13/33



F-6-98
San Marino

Frederick Co., MD

E. Wallace

403

MD SHPO

Dairy barn, S elevation, view N

14/
33



F-6-98

San Marino

Frederick Co., MD

E. Wallace

1/03

MDSDPO

Dairy barn, interior, view toward NE corner

15/33



F-6-a3

San Marino

Frederick Co., MD


E. Wallace

1/03

MDSTHO

Milk house, W and S elevations, view NE

16/33



F-6-98

San Marino

Frederick Co., MD

E. Wallace

1/03

MD SHPO

Milk house, interior, milk storage tank

17/
33



F-6-98

San Marino

Fredrick Co., MD

E. Wallace

1-03

MDSTRIPD

Cow stall barn and NW corner of Utility barn
showing old bank barn wall, view E

18/33



F-6-98

San Marino

Frederick Co., MD

E. Wallace

1/03

MD 5470

Cow stall barn view W

19/33



F-6-98

San Marino

Frederick Co., MD

E. Wallace

1/03

MD SHPO

Utility barn and Dairy barn, corral in front
view NW

20/33



F-6-98

San Marino

Frederick Co., MD

E. Wallace

1/03

MD SHPO

Utility barn, interior showing steel pipe
Framing, view toward W wall

21/33



F-6-98

San Marino

Frederick Co., MD


E. Wallace

1/03

MDSHPO

Ensilage building, view E

22/33



F-6-98

San Marino

Frederick Co., MD

E Wallace

1/03

MD SHPO

Work shop, S elevation, view NW

23/33



F-6-98

San Marino

Frederick Co., MD

E. Wallace

1/03

MDSHTO

Workshop, interior, view toward NW corner

24/33



F-6-98

San Marino

Frederick Co., MD

E. Wallace

1-03

MSHPD

Wagon shed/corn crib, E elevation, view NW

25/
33



F-6-98

San Marino

Frederick Co, MD

E. Wallace

1/03

MDSHPD

Wagon shed/corncrib, S elevation, view N

26/33



F-6-98

San Marino

Frederick Co, MD

E. Wallace

1/03

MD SHPO

Wagon shed/cornerib, E wall interior

27/33



F-6-98

San Marino

Frederick Co. (H.D.)

E. Wallace

1-03

MDSHIP

Stone + frame storage bldg, W and S elevations,
view NE

28/
33



F-6-98

San Marino

Frederick Co., MD

E. Wallace

1-03

MDSHPO

Hog pen and corn crib, view SE

29/33



F-6-98

Son Marins

Frederick Co., MD

E. Wallace

1.03

MISSHO

Equipment quonset, view NW

30/33



F-6-98

San Marino

Frederick Co., MD

E. Wallace

1-03

MDSHPO

Farm setting, view N from quonset

31/33



F-6-98

San Marino

Frederick Co. - 1915

E. Wallace

1-03

MASHPO

Free stalls, view W

32/33



F-6-98

San Marino

Frederick Co., MD

Er Wallace

1/03

MD SHPO

Form setting, view S toward quarry site

33/33

F-6-98

Ca. 1812, 1853

San Marino

Emmitsburg vicinity

Private

San Marino is located on the south side of Motter's Station Road. The house is surrounded by agricultural fields with the Catoclin Mountains situated directly west. The principal gable is oriented on a north-west axis. The property includes distinctive domestic and agricultural outbuildings such as a Gothic Revival "privy", a stone garage/early dwelling and a pyramidal hipped roof smokehouse. San Marino is significant as an elegant dwelling house that has incorporated original Georgian elements with later Victorian period embellishments and changes. Domestic outbuildings accompanying the main house contribute to this significance. In comparison to regional farmhouses, the house shows architectural distinction. San Marino is also important in representing extensive farming operations that have continued to present day. These operations have spanned a period of at least one hundred years as evidenced in the agricultural outbuildings.

F-6-98
San Marino
Emmitsburg, Maryland
Frederick County

HISTORIC CONTEXT:

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA

Geographic Organization: Piedmont
(Harford, Baltimore, Carroll, Frederick, Howard, Montgomery Counties,
and Baltimore City)

Chronological/Development Period:
Rural Agrarian Intensification 1680-1815 A.D.
Agricultural-Industrial Transition 1815-1870 A.D.
Industrial/Urban Dominance 1870-1930 A.D.
Modern Period

Prehistoric/Historic Period Themes:
Architecture, Landscape Architecture and Community Planning
Agriculture

Resource Type:
Category: Buildings

Historic Environment: Rural

Historic Function and Use:
Domestic/single dwelling/residence
Domestic/secondary structure/privy, smokehouse, garage, wood shed
Agricultural/Subsistence/agricultural outbuilding/barns, dairy,
sheds

Known Design Source: None

Maryland Historical Trust
State Historic Sites Inventory Form

**MARYLAND INVENTORY OF
HISTORIC PROPERTIES**

Survey No. F-6-98

Magi No.

DOE ☐ yes ☐ no

1. Name (indicate preferred name)

historic San Marino

and/or common

2. Location

street & number 15828 Motter's Station Road ☐ not for publication

city, town Emmitsburg ☒ vicinity of congressional district 6th

state Maryland county Frederick

3. Classification

Category	Ownership	Status	Present Use
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input checked="" type="checkbox"/> agriculture
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational
<input type="checkbox"/> site	Public Acquisition	Accessible	<input checked="" type="checkbox"/> private residence
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> religious
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> scientific
	<input checked="" type="checkbox"/> not applicable	<input type="checkbox"/> no	<input type="checkbox"/> transportation
			<input type="checkbox"/> other:

4. Owner of Property (give names and mailing addresses of all owners)

name Donald E. Moser

street & number 15828 Motter's Station Road telephone no.:

city, town Emmitsburg state and zip code MD 21727

5. Location of Legal Description

courthouse, registry of deeds, etc. Frederick County Courthouse liber 462

street & number 100 W. Patrick Street folio 101

city, town Frederick state MD 21701

6. Representation in Existing Historical Surveys

title Anthony James Survey

date 1974 ☐ federal ☐ state ☐ county ☒ local

depository for survey records Frederick County Dept. Planning & Zoning

city, town Frederick state MD 21701

7. Description

Survey No. F-6-98

Condition

☐ excellent
☐ good
☒ fair

☐ deteriorated
☐ ruins
☐ unexposed

Check one

☐ unaltered
☒ altered

Check one

☒ original site
☐ moved

date of move _____

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

(Typed on separate sheet)

8. Significance

Survey No. F-6-98

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input checked="" type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates

Builder/Architect

check: Applicable Criteria: ☐ A ☐ B ☒ C ☐ D
and/or

Applicable Exception: ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G

Level of Significance: ☐ national ☒ state ☐ local

Prepare both a summary paragraph of significance and a general statement of history and support.

(Typed on separate sheet)

9. Major Bibliographical References

Survey No. F-6-98

Atlas of Frederick County, Maryland, C.O. Titus and Co., Philadelphia, 1873.

Interview with current owner, May 1991.

Map of Frederick County, Maryland, Isaac Bond, Baltimore, 1858.

San Marino File, Frederick County Department of Planning and Zoning.

Williams, T.J. C. History of Frederick County, Maryland, L.R. Titworth & Co., Frederick, Md.

10. Geographical Data

Acreage of nominated property 187.14 acres

Quadrangle name Emmitsburg, MD Quadrangle

Quadrangle scale 1:24000

UTM References do NOT complete UTM references

A

--	--	--	--	--	--	--	--	--	--

Zone Easting NorthingB

--	--	--	--	--	--	--	--	--	--

Zone Easting NorthingC

--	--	--	--	--	--	--	--	--	--

D

--	--	--	--	--	--	--	--	--	--

E

--	--	--	--	--	--	--	--	--	--

F

--	--	--	--	--	--	--	--	--	--

G

--	--	--	--	--	--	--	--	--	--

H

--	--	--	--	--	--	--	--	--	--

Verbal boundary description and justification

Tax Map 14, Parcel 7

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
-------	------	--------	------

state	code	county	code
-------	------	--------	------

11. Form Prepared By

name/title Mary Kendall Shipe, Historic Sites Surveyor

organization Frederick County Planning & Zoning Dept. date July, 1991

street & number 12 E. Church Street telephone 696-2958

city or town Frederick state MD 21701

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
Shaw House
21 State Circle
Annapolis, Maryland 21401
(301) 269-2438

MARYLAND HISTORICAL TRUST
DHCP/DHCD
100 COMMUNITY PLACE
CROWNSVILLE, MD 21032-2023
301-514-7600

7.1 Description:

San Marino is located on the south side of Motter's Station Road in the vicinity of Emmitsburg, Maryland. The house is surrounded by agricultural fields with the Catoclin Mountains situated directly west. The principal gable is oriented on a north-west axis. The property includes distinctive domestic and agricultural outbuildings such as a Gothic Revival "privy", a stone garage/early dwelling and a pyramidal hipped roof smokehouse.

The house was constructed in two stages; the first stage was circa 1812 with a later stage circa 1853. The main block of the house was originally constructed as a Georgian dwelling house, 2 stories of flemish bond and common bond brick construction. There are a water table and a belt course (3 raised courses) on the main facade. The gable roof is covered in composition shingling. There are two interior end brick chimneys that are double stacked. The later stage included decorative changes and additions such as bargeboard trim, turned spindles and French doors. It also included a 2 story rear ell. Covered in stucco, the ell has a gable roof sheathed in composition shingling with one interior end brick chimney and is three bays wide.

The principal facade of the house faces east. There are 4 symmetrical bays. The first floor has 4 French doors with gauged flat arches; the second floor has 6/6 windows with jack arches. There are two gabled dormers with paired windows, 3 lights in each. A one story open porch extends across the facade and wraps around part of the north elevation. It is raised on brick piers with latticework in between the piers. It has a standing seam metal hipped roof, chamfered columns, bracketing and supports.

The north gable end has bargeboard and finials at the eaves and the gable peak. It is two bays wide. The first floor has two door openings: one door has a 2 light transom, 8 pane sidelights and a decorative panel design, the other is a French door. Second floor windows are closed with shutters. The attic level has two "half-moon" windows. The south gable end is also two bays wide. It has the same eaveline treatment as the north end with bargeboard and finials. It has 6/6 windows on the first and second floors and "half-moon" attic windows.

The main facade of the rear ell faces north and is 3 bays wide. It is slightly recessed from the main block. There is a double porch with latticework and bracketing that is flush with the main block. The first story has two French doors and a side door with a 6 light transom. The second story has 9/6 windows and a door with a 6 light transom. Two gabled dormers have 3 light paired windows. A one story stuccoed addition with a hipped roof extends to the west: it has a side door with a hipped roof entry porch and one 1/1 window.

7.2 Description:

The south elevation is also 3 bays. The first floor has one 9/6 window and a French door with center placement. The door has a hipped roof entry porch with square columns and bracketing. The second floor has two 9/6 windows and one 2/2 window.

The west gable end of the rear ell is partially stuccoed and partially weatherboarded. It has an attic window that is shuttered closed. The second story of the porch is enclosed with weatherboard and has a 9/6 window. The one story addition is sheathed in plywood. It has two 1/1 windows.

Outbuildings include the following:

Gothic Revival Privy: Located several feet southwest of the house, this one story building has a gable-front roof and faces east. The roof is covered in corrugated tin. The building is sheathed in board and batten siding. A decorative scroll bargeboard is beneath the cornice. The east gable front has a pointed arch door. There are two 6 light fixed windows in the north elevation. The west elevation has a less elaborate arched door opening.

Smokehouse: Situated to the northwest of the house, this is a one story stone building with a pyramidal hipped roof. There is brick corbelling in the eaves. A plank door in the south elevation is the only opening.

Stone Outbuilding: This building is situated several feet north of the house. It may have been utilized as a blacksmith's shop, slave quarters, or an earlier dwelling house. At some point, it functioned as a garage. It is a one story stone building with a gable roof of standing seam tin. It has one interior end brick chimney. There is large stone quoining at the corners. The west elevation has three 6/6 windows and a center door. The east elevation is covered with a frame enclosure. The south gable end has board and batten siding and a 6/6 window in the upper half and stone in the lower half. The north gable end is stone except for the eastern bay which is open as a entry.

Concrete Block Barn and Dairy Shed: Located several yards north of the house, the barn and dairy shed have barrel roofs with flared eaves. The roofs are sheathed in corrugated tin. They are covered in formstone and have vertical siding in the gable ends.

Other outbuildings include a new wood shed of board and batten siding with a gable roof of corrugated tin, two agricultural sheds and a frame barn.

8.1 Significance:

San Marino is significant as an elegant dwelling house that has incorporated original Georgian elements with later Victorian period embellishments and changes. Domestic outbuildings accompanying the main house contribute to this significance. In comparison to regional farmhouses, the house shows architectural distinction. San Marino is also important in representing extensive farming operations that have continued to present day. These operations have spanned a period of at least one hundred years as evidenced in the agricultural outbuildings.

Considered within its historic context, San Marino is an unusual house in a region where vernacular buildings are dominant. It clearly demonstrates the influence of high-style architecture and is an important building in the region. At least two other houses in close proximity share similar features with San Marino: Hayland Farm and Thornbrook Farm. All three of these houses probably had associations with nearby Mount Saint Mary's College and may have been designed by the same architect. Further analysis of the buildings as a collective group should be undertaken.

By the mid-nineteenth century, Joshua Shorb had purchased San Marino which was a farm of 207 acres with buildings and improvements. After a brief ownership, Shorb apparently moved to California and became a founder of the city, San Marino, named for his former Maryland residence. It was probably under his ownership (1853-1858) that the house underwent the Gothic Revival and Victorian changes. In 1895, the house was described in the Frederick News as having "a fine dwelling house and necessary outbuildings and is particularly well adapted for a stock farm." (San Marino File, FCDP&Z) By 1900, Daniel Roddy, a lime-kiln owner, had acquired San Marino. Under Roddy ownership, it was described as "a beautiful farm of 200 acres, almost all under cultivation." (Williams, Vol.II, p.1013)

MARYLAND HISTORICAL TRUST WORKSHEET

MAGI

1102275935

F-6-98

F-5-199

NOMINATION FORM

for the
NATIONAL REGISTER OF HISTORIC PLACES, NATIONAL PARKS SERVICE

1. NAME

COMMON:

SAN MARINO



AND/OR HISTORIC:

2. LOCATION

STREET AND NUMBER:

WEST SIDE OF MOTTERS STATION ROAD (MD 76) 1/2 mi SOUTH OF US 15

CITY OR TOWN:

EMITTSBURG ELECTION DISTRICT

STATE:

COUNTY:

3. CLASSIFICATION

CATEGORY (Check One)		OWNERSHIP		STATUS	ACCESSIBLE TO THE PUBLIC
<input type="checkbox"/> District	<input checked="" type="checkbox"/> Building	<input type="checkbox"/> Public	Public Acquisition:	<input checked="" type="checkbox"/> Occupied	Yes:
<input type="checkbox"/> Site	<input type="checkbox"/> Structure	<input checked="" type="checkbox"/> Private	<input type="checkbox"/> In Process	<input type="checkbox"/> Unoccupied	<input type="checkbox"/> Restricted
<input type="checkbox"/> Object		<input type="checkbox"/> Both	<input type="checkbox"/> Being Considered	<input type="checkbox"/> Preservation work in progress	<input type="checkbox"/> Unrestricted
<input checked="" type="checkbox"/> No					

PRESENT USE (Check One or More as Appropriate)

<input type="checkbox"/> Agricultural	<input type="checkbox"/> Government	<input type="checkbox"/> Park	<input type="checkbox"/> Transportation	<input checked="" type="checkbox"/> Comments
<input type="checkbox"/> Commercial	<input type="checkbox"/> Industrial	<input checked="" type="checkbox"/> Private Residence	<input type="checkbox"/> Other (Specify)	NEEDS
<input type="checkbox"/> Educational	<input type="checkbox"/> Military	<input type="checkbox"/> Religious		HELP
<input type="checkbox"/> Entertainment	<input type="checkbox"/> Museum	<input type="checkbox"/> Scientific		

4. OWNER OF PROPERTY

OWNER'S NAME:

MOSER

STREET AND NUMBER:

CITY OR TOWN:

STATE:

5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC:

STREET AND NUMBER:

CITY OR TOWN:

STATE:

Title Reference of Current Deed (Book & Pg. #):

6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY:

DATE OF SURVEY:

☐ Federal

☐ State

☐ County

☐ Local

DEPOSITORY FOR SURVEY RECORDS:

STREET AND NUMBER:

CITY OR TOWN:

STATE:

SEE INSTRUCTIONS

F-5-199

OLD

7. DESCRIPTION

CONDITION

☐ Excellent☐ Good☒ Fair

(Check One)

☐ Deteriorated☐ Ruins☐ Unexposed

(Check One)

☒ Altered☐ Unaltered

(Check One)

☐ Moved☒ Original Site

DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE

2½ STORY VICTORIANIZED BRICK WITH STUCCOED REAR WING.

BRICKWORK:

MAIN (EAST) FACADE: FLEMISH BOND (with QUEEN CLOSERS)
WATER TABLE
BELT COURSE (3 bricks high)

OTHER FACADES: COMMON BOND OR STUCCOED

3 VICTORIAN BRICK CHIMNEYS

SAWN TRIM AROUND EAVES

6 TURNED SPINDLES ON MAIN GABLES



EAST (MAIN) FACADE: 4 BAYS WIDE 1st FLOOR PORCH

4 FRENCH DOORS
GAUGED FLAT ARCHES

SOUTH FACADE: STUCCOED
GREAT SAWN BARGE BOARDS

MAIN BLOCK: 2 BAYS WIDE
6/6 WINDOWS

WING: 3 BAYS
9/6 WINDOWS

CENTRAL 6 panel door, 3 light transom

behind this door, recessed, a 6-light french door

1 STORY PORCH

1 STORY CLAPBOARD SHED ADDITION:

2 BAYS
DOOR IN EAST BAY

WEST FACADE: MAIN BLOCK: 1 BAY (6/9)

WING: 1 ATTIC WINDOW W/ BLINDS

ADDITION: 2 BAYS

NORTH FACADE: MAIN BLOCK: 2 BAYS

DOOR IN WESTERN BAY
3 PANE SIDE LIGHTS
2 LIGHT TRANSOM

WINDOWS HAVE BLINDS

2 ATTIC WINDOWS

CONTINUATION OF
1st FLOOR PORCH OF EAST FACADE

WING: 3 BAYS

1st FLOOR: 3 FRENCH DOORS

EASTERN BAY HAS 6-LIGHT TRANSOM



ROOF NEEDS REPAIR BADLY

SEE INSTRUCTIONS

8. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

☐ Pre-Columbian☐ 16th Century☒ 18th Century☐ 20th Century☐ 15th Century☐ 17th Century☒ 19th Century

SPECIFIC DATE(S) (If Applicable and Known)

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

☐ Aboriginal☐ Education☐ Political☐ Urban Planning☐ Prehistoric☐ Engineering☐ Religion/Phi-☐ Other (Specify)☐ Historic☐ Industry☐ losophy☐ Agriculture☐ Invention☐ Science☒ Architecture☐ Landscape☐ Sculpture☐ Art☐ Architecture☐ Social/Human-☐ Commerce☐ Literature☐ itarian☐ Communications☐ Military☐ Theater☐ Conservation☐ Music☐ Transportation

STATEMENT OF SIGNIFICANCE

FROM AN ELEGANT GEORGIAN BEGINNING TO ELABORATE
VICTORIAN ALTERATIONS: ALL AROUND A FINE HOUSE
WITH A GOOD SET OF OUTBUILDINGS

DEFINITELY WORTHY OF FURTHER RESEARCH.

DESCRIPTION CONT

STONE BLACKSMITH SHOP ?
SLAVE QUARTERS ?

BOX CORNICE

1 BRICK CHIMNEY
ALTERED

SQUARE STONE SMOKEHOUSE
BRICK CORNICE
PYRAMIDAL ROOF

GOthic BOARD & BATTEN
"CHapel of Ease" PRIVY
SILVER TRIM

E: POINTED ARCH DOORWAY

N.T.S. 2 BAYS

W: DOORWAY WITH



POINTED
ARCH
APPLIED

FRAME BARN

MID 19th C.



PRIVY

STONE
TRASH
PIT

N
↓



SMOKEHOUSE

STONE
BLACKSMITH ?
SLAVE Q.



BARN

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY				O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES			
CORNER	LATITUDE				LONGITUDE			
	Degrees	Minutes	Seconds		Degrees	Minutes	Seconds	
NW	0	'	"		0	'	"	
NE	0	'	"		0	'	"	
SE	0	'	"		0	'	"	
SW	0	'	"		0	'	"	

APPROXIMATE ACREAGE OF NOMINATED PROPERTY:

Acreage Justification:

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:		COUNTY:	
STATE:		COUNTY:	
STATE:		COUNTY:	
STATE:		COUNTY:	

11. FORM PREPARED BY

NAME AND TITLE:	
ORGANIZATION	DATE
STREET AND NUMBER:	
CITY OR TOWN:	STATE

12. State Liaison Officer Review: (Office Use Only)

Significance of this property is:

National ☐ State ☐ Local ☐

Signature _____


SEE INSTRUCTIONS


EMMITTSBURG

DIST No. 3

Scale 1 1/2 inches to the mile

F-6-98
 San Marino
 Emmittsburg vicinity
 Frederick County
 Atlas of Frederick County, Maryland, C.O.
 Titus and Co., Philadelphia, 1873.





Joins Map 4

Joins Map 8

©MCMXXXVI-ADC
COPYRIGHT MCMXXXVI-ADC
MD GRID 710,000 FT

DAK 5062 PX

14

KODAK 5062 PX



Die 13A

14

DAK 5062 PX



Die 14A

15

3 of

F-6-98
~~F-5-199~~

9.25.90 Andrews

1A

2

2A

3

3A

4

4A

5

5A

6

6A

7



1A 2 2A 3 3A 4 4A 5 5A 6 6A 7

5 KODAK 5062 PX 6 KODAK 5062 PX 7 KODAK 5062 PX

16252

SW

F-6-98

~~F-5-199~~

W elev

9.25.90

Andrews



7A

8

KODAK 5062 PX



9

KODAK 5062 PX



10

KODAK 5062 PX



11

KODAK 5062 PX



12

KODAK 5062 PX



13

NE

F-6-98

F-5-199

SE el

9.25.90

Andrews

meat hse



F-6-98

San Marino

15828 Motters Station Road

Emmitsburg vicinity

Fredenck County

Photo: MARY K SHIPE

May 1991

Neg. loc: MHT

northeast corner view

1/6



F-6-98

San Marino

15828 Motters Station Road

Emmitsburg vicinity

Fredrick County

Photo: MARY K SHIPE

May 1991

Neg. loc: MHT

northeast corner view

2/4



F-6-98

San Marino

15828 Motters Station Road

Emmitsburg vicinity

Fredenck County

Photo: MARY K SHIPE

May 1991

Neg. loc: MHT

Gothic Revival Privy - East elev.

3/6



F-6-98

San Marino

15828 Motters Station Road

Emmitsburg vicinity

Frederick County

Photo: MARY K SHIPE

May 1991

Neg. loc: MHT

Smokehouse - S.W. corner view

4/6



F-6-98

San Marino

15828 Motters Station Road

Emmitsburg vicinity

Fredrick County

Photo: MARY K. SHIPE

May 1991

Neg. loc: MHT

stone outbldg - northwest corner view

5/6



F-6-98

San Marino

15828 Motters Station Road

Emmitsburg vicinity

Fredrick County

Photo: MARY K SHIPE

May 1991

Neg. loc: MHT

dairy barn + shed - east elev.

6/6